



3250 Linebaugh Rd.
 Xenia, OH 45385
 Telephone (800) 762-0040
 FAX (937) 879-8425

**CEMENT
MILL
TEST**

Cement Identified as: **Type III** **Date:** **08/31/20**
Production Dates: **July, 2020** **Silo:** **3**

STANDARD CHEMICAL REQUIREMENTS (ASTM C 114)	SPECIFICATIONS	ASTM C 150 TYPE III	AASHTO M85 Type III	RESULTS
Silicon Dioxide (SiO ₂), %		----		18.7
Aluminum Oxide (Al ₂ O ₃), %		----		4.5
Ferric Oxide (Fe ₂ O ₃), %		----		3.1
Calcium Oxide (CaO), %		----		61.8
Magnesium Oxide (MgO), %	Maximum	6.0	6.0	4.6
Sulfur Trioxide (SO ₃), % ^A	Maximum	3.5	3.5	4.1
Loss on Ignition (LOI), %	Maximum	3.5	3.5	2.2
Insoluble Residue, %	Maximum	1.50	1.5	0.50
Free Calcium Oxide, %				0.8
Alkalies (Na ₂ O equivalent), %		----		0.83
Tricalcium Silicate (C ₃ S), Potential %		----		63
Dicalcium Silicate (C ₂ S), Potential %		----		6
Tricalcium Aluminate (C ₃ A), Potential %	Maximum	15	15	7
Tetracalcium Aluminoferrite (C ₄ AF), Potential %		----		9
CO ₂ , %				0.9
Limestone, %	Maximum	5.0	5.0	2.0
CaCO ₃ in Limestone, %	Minimum	70	70	97
PHYSICAL REQUIREMENTS				
(ASTM C 204) Blaine Fineness, m ² /kg		----		645
(ASTM C 191) Time of Setting (Vicat)				
Initial Set, minutes	Minimum	45	45	81
Final Set, minutes	Maximum	375	375	175
(ASTM C 185) Air Content, %	Maximum	12	12	7
(ASTM C 151) Autoclave Expansion, %	Maximum	0.80	0.80	0.13
(ASTM C 1038) Expansion in Water, %	Maximum	0.02	0.02	0.013
(ASTM C 187) Normal Consistency, %		----		29.4
(ASTM C 109) Compressive Strength, psi (Mpa)				
1 Day	Minimum	1740 (12.0)	1740 (12.0)	4486 (30.9)
3 Day	Minimum	3480 (24.0)	3480 (24.0)	5496 (37.9)
7 Day		----		6140 (42.3)
28 Day		----		6746 (46.5)

^A Per ASTM C150 Table 1 footnote D

We hereby certify that this cement conforms to all of the standard requirements for portland cement in the above specification for the type specified.

By: Rusty Strader

Physical Testing completed by: DG, MS
 Chemical Testing completed by: TA, NC, JD, NM

Rusty Strader
 Quality Control Manager
 Fairborn Cement Company



3250 Linebaugh Rd.
Xenia, OH 45385
Telephone (800) 762-0040
FAX (937) 879-8425

**CEMENT
MILL
TEST**

Cement Identified as: Type III **Date:** 08/31/20
Production Period: July, 2020 **Silo:** 3

Additional Data

Type	Inorganic Processing	
	Addition Data	Limestone
Amount (%)	Baghouse Dust	---
SiO ₂ (%)	0.0	2.0
Al ₂ O ₃ (%)	11.6	0.9
Fe ₂ O ₃ (%)	4.2	0.6
CaO (%)	1.6	0.6
SO ₃ (%)	37.7	45.9
	0.7	0.2

Base cement Phase Composition

C3S (%)	59
C2S (%)	9
C3A (%)	7
C4AF (%)	9

We hereby certify that this cement conforms to all of the standard requirements for portland cement in the above specification for the type specified.

By: *Rusty Strader*

Rusty Strader
Quality Control Manager
Fairborn Cement Company