

3250 Linebaugh Rd. Xenia, OH 45385 Telephone (800) 762-0040 FAX (937) 879-8425

## CEMENT MILL TEST

Date: 09/30/21

**Cement Identified as:** 

**Mortar Cement, Type S** 

**Production Dates:** 

August, 2021

PHYSICAL REQUIREMENTS	ASTM C 1329 SPECIFICATIONS Type S		5
			RESULTS
(ASTM C 420) 45 ym giovo 0/ mateinad	Maximum	24	9
(ASTM C 430) 45-um sieve, % retained			
(ASTM C 151) Autoclave Expansion, %	Maximum	1.0	0.09
(ASTM C 266) Time of Setting (Gillmore)			
Initial Set, minutes	Minimum	90	190
Final Set, minutes	Maximum	1000	275
(ASTM C 185) Air Content, %	Range	8-19	14
(ASTM C 1506) Water Retention	Minimum	70	81
(ASTM C1072) Flexural Bond Strength (psi)	Minimum	100	102
(ASTM C 109) Compressive Strength, psi (Mpa)			
7 Day	Minimum	1300 ( 3.5 )	2640 ( 18.2 )
28 Day	Minimum	2100 ( 14.5 )	3020 ( 20.8 )

We hereby certify that this cement conforms to all of the standard requirements for mortar cement in the above specification for the type specified. ASTM C1072 testing is performed by an independent testing firm and results are available upon request.

Bv.

Physical Testing completed by: DG, MS

Chemical Testing completed by: TA, NC, KL, NM

Rusty Strader Quality Control Manager Fairborn Cement Company

Rusty Strader