



3250 Linebaugh Rd.
 Xenia, OH 45385
 Telephone (800) 762-0040
 FAX (937) 879-8425

**CEMENT
MILL
TEST**

Cement Identified as: Type I, Type II **Date:** 02/02/22

Production Period: December, 2021 **Silos:** 2, 6

STANDARD CHEMICAL REQUIREMENTS (ASTM C 114)	SPECIFICATIONS	ASTM C 150		AASHTO	RESULTS
		TYPE I	TYPE II (MH)	M85 Type I	
Silicon Dioxide (SiO ₂), %		-----	-----	-----	19.2
Aluminum Oxide (Al ₂ O ₃), %	Maximum	-----	6.0	-----	4.4
Ferric Oxide (Fe ₂ O ₃), %	Maximum	-----	6.0	-----	3.2
Calcium Oxide (CaO), %		-----	-----	-----	62.0
Magnesium Oxide (MgO), %	Maximum	6.0	6.0	6.0	4.4
Sulfur Trioxide (SO ₃), % ^A	Maximum	3.0	3.0	3.0	3.3
Loss on Ignition (LOI), %	Maximum	3.5	3.5	3.5	2.7
Insoluble Residue, %	Maximum	1.50	1.50	1.5	0.62
Alkalies (Na ₂ O equivalent), %		-----	-----	-----	0.75
Tricalcium Silicate (C ₃ S), Potential %		-----	-----	-----	60
Dicalcium Silicate (C ₂ S), Potential %		-----	-----	-----	7
Tricalcium Aluminate (C ₃ A), Potential %	Maximum	-----	8	-----	6
Tetracalcium Aluminoferrite (C ₄ AF), Potential %		-----	-----	-----	9
C ₃ S + 4.75C ₃ A	Maximum		100		89
CO ₂ , %					1.6
Limestone, %	Maximum	5.0	5.0		3.8
CaCO ₃ in Limestone, %	Minimum	70	70		97
PHYSICAL REQUIREMENTS					
(ASTM C 204) Blaine Fineness, m ² /kg	Range	260 Min.	260 - 430	260 Min.	390
(ASTM C 191) Time of Setting (Vicat)					
Initial Set, minutes	Minimum	45	45	45	113
Final Set, minutes	Maximum	375	375	375	216
(ASTM C 185) Air Content, %	Maximum	12	12	12	7
(ASTM C 151) Autoclave Expansion, %	Maximum	0.80	0.80	0.80	0.10
(ASTM C 1038) Expansion in Water, %	Maximum	0.02	0.02	0.02	0.005
(ASTM C 187) Normal Consistency, %		-----	-----	-----	25.8
Heat of Hydration (ASTM C 1702)					
3 day, cal/g	Most Recent Value				82
(ASTM C 109) Compressive Strength, psi (Mpa)				-----	
1 Day		-----	-----	-----	2496 (17.2)
3 Day	Minimum	1740 (12.0)	1450 (10.0)	1740 (12.0)	4278 (29.5)
7 Day	Minimum	2760 (19.0)	2470 (17.0)	2760 (19.0)	5201 (35.9)
28 Day	Minimum	4060 (28.0)	4060 (28.0)	4060 (28.0)	6390 (44.1)

^A Per ASTM C150 Table 1 footnote D

We hereby certify that this cement conforms to all of the standard requirements for portland cement in the above specification for the type specified.

By: Rusty Strader

Physical Testing completed by: DG, JT
 Chemical Testing completed by: TA, NC, KL, NM

Rusty Strader
 Quality Control Manager
 Fairborn Cement Company



3250 Linebaugh Rd.
 Xenia, OH 45385
 Telephone (800) 762-0040
 FAX (937) 879-8425

**CEMENT
MILL
TEST**

Cement Identified as: **Type I, Type II** **Date:** 02/02/22

Production Period: **December, 2021** **Silos: 2, 6**

Additional Data

Type Amount (%)	Inorganic Processing Addition Data	Limestone
	Baghouse Dust	Limestone
SiO ₂ (%)	0.7	3.8
Al ₂ O ₃ (%)	13.6	2.6
Fe ₂ O ₃ (%)	4.7	1.1
CaO (%)	2.0	0.6
SO ₃ (%)	41.5	50.4
	1.1	0.4

Base cement Phase Composition

C3S (%)	56
C2S (%)	12
C3A (%)	6
C4AF (%)	10

We hereby certify that this cement conforms to all of the standard requirements for portland cement in the above specification for the type specified.

By: *Rusty Strader*

Rusty Strader
 Quality Control Manager
 Fairborn Cement Company