



3250 Linebaugh Rd.  
 Xenia, OH 45385  
 Telephone (800) 762-0040  
 FAX (937) 306-4110

**CEMENT  
MILL  
TEST**

**Cement Identified as:** API Class A **Date:** 03/31/22

**Plant:** Fairborn Cement Company  
**Production Period:** March, 2022 **Silo: 4**

STANDARD CHEMICAL REQUIREMENTS (ASTM C 114)		API SPECIFICATION CLASS A		RESULTS
Silicon Dioxide (SiO <sub>2</sub> ), %		-----		20.1
Aluminum Oxide (Al <sub>2</sub> O <sub>3</sub> ), %		-----		4.6
Ferric Oxide (Fe <sub>2</sub> O <sub>3</sub> ), %		-----		3.3
Calcium Oxide (CaO), %		-----		62.7
Magnesium Oxide (MgO), %	Maximum			4.6
Sulfur Trioxide (SO <sub>3</sub> ), %	Maximum	3.0		2.9
Loss on Ignition (LOI), %	Maximum	3.5		1.0
Insoluble Residue, %	Maximum	1.50		0.44
Alkalies (Na <sub>2</sub> O equivalent), %		-----		0.79
Tricalcium Silicate (C <sub>3</sub> S), Potential %		-----		59
Dicalcium Silicate (C <sub>2</sub> S), Potential %		-----		14
Tricalcium Aluminate (C <sub>3</sub> A), Potential %	Maximum	-----		7
Tetracalcium Aluminoferrite (C <sub>4</sub> AF), Potential %		-----		10
<b>PHYSICAL REQUIREMENTS</b>				
(ASTM C204) Blaine Fineness, m <sup>2</sup> /kg	Minimum	280		298
API Compressive Strength, psi (Mpa)				
8 Hour, 100 degree F	Minimum	250 (1.7)		1155 ( 8.0 )
24 Hour, 100 degree F	Minimum	1800 (12.4)		3590 ( 24.8 )
API Schedule 4 Thickening Time, minutes	Minimum	90		119
Maximum Consistency, 15 - 30				13

We hereby certify that this cement conforms to the standard requirements for API Specification 10A.

By: \_\_\_\_\_

Physical Testing completed by: DG , JT  
 Chemical Testing completed by: TA, NM, NC, KL

Rusty Strader  
 Quality Control Manager  
 Fairborn Cement Company