



3250 Linebaugh Rd.
 Xenia, OH 45385
 Telephone (800) 762-0040
 FAX (937) 306-4110

**CEMENT
MILL
TEST**

Cement Identified as: API Class A **Date:** 07/01/22
Plant: Fairborn Cement Company
Production Period: June, 2022 **Silo:** 4

STANDARD CHEMICAL REQUIREMENTS (ASTM C 114)		API SPECIFICATION CLASS A		RESULTS
Silicon Dioxide (SiO ₂), %		-----		19.8
Aluminum Oxide (Al ₂ O ₃), %		-----		4.7
Ferric Oxide (Fe ₂ O ₃), %		-----		3.2
Calcium Oxide (CaO), %		-----		62.0
Magnesium Oxide (MgO), %	Maximum			4.5
Sulfur Trioxide (SO ₃), %	Maximum	3.0		2.9
Loss on Ignition (LOI), %	Maximum	3.5		1.1
Insoluble Residue, %	Maximum	1.50		0.31
Alkalies (Na ₂ O equivalent), %		-----		0.86
Tricalcium Silicate (C ₃ S), Potential %		-----		58
Dicalcium Silicate (C ₂ S), Potential %		-----		13
Tricalcium Aluminate (C ₃ A), Potential %	Maximum	-----		7
Tetracalcium Aluminoferrite (C ₄ AF), Potential %		-----		10
PHYSICAL REQUIREMENTS				
(ASTM C204) Blaine Fineness, m ² /kg	Minimum	280		306
API Compressive Strength, psi (Mpa)				
8 Hour, 100 degree F	Minimum	250 (1.7)		1143 (7.9)
24 Hour, 100 degree F	Minimum	1800 (12.4)		3137 (21.6)
API Schedule 4 Thickening Time, minutes	Minimum	90		114
Maximum Consistency, 15 - 30				11

We hereby certify that this cement conforms to the standard requirements for API Specification 10A.

By: Rusty Strader

Physical Testing completed by: DG , JT
 Chemical Testing completed by: TA, NM, NC, KL

Rusty Strader
 Quality Control Manager
 Fairborn Cement Company